No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
5	Cutting and forming the road between 3+4/8 mile	C.yd.	0 3 6	1,823	
6	Carting the above quantity and forming bank with an average lead ¼ mile	,,	0 2 6	1,823	
7	Earth cutting sides and check drains and using the earth for formation of road including lead as per detail estimates	,,	0 3 6	23,317	
8	Excavation of shoulder drains and using the earth for the embankment of the road with lead	Fur.	4 0 0	83	
9	Mile stones neatly dressed, cutting figures, painting, etc., complete as per specification	Each	10 0 0	11	
10	Furlong stones do	,,	3 0 0	73	
11	Turfing the banks wherever necessary *(Rate per sq. yd. to be quoted)	L.S.			150
12	Collection and consolidation of gravel	C.yd.	0 6 0	4,565	
13	Lead charges 0 to 4 miles ½ length average 2 miles.	,,	0 14 0	440	
14	Do 4 to 8 miles ½ length average 1 mile.	,,	0 8 0	880	
15	Removing ant hills, blasting out rocks here and there	L.S.	..	..	150
16	Providing R. C. finger post	Each	50 0 0	2	
17	Constructing masonry tunnels, *vide* details given below :—				
	No. 12 to be constructed, vide detailed plan.				
	(*a*) Earthwork excavation	C.yd.	0 4 0	30	
	(*b*) Concrete in surki mortar	C.ft.	0 4 6	196	
	(*c*) Size stone in surki mortar	C.ft.	0 6 0	238	
	(*d*) Burnt stone slabs 6" thick, dressed and fixed over the ventway	Sq.ft.	0 10 0	99	
	(*e*) Pointing with cement mortar	Sqr.	4 8 0	1.55	
	(*f*) Building stone-slabbed parapet wall nicely dressed and fixed in cement including cement pointing, cutting grooves wherever necessary	Sq.ft.	1 0 0	26	
18	Providing metalled wheel-tracks 4'—6" centres and 1 ft. wide of about 3" metal, etc., complete wherever necessary	L.S.	..	..	5,000
	*Rates per C.yd. for quartz metal collection and rate for consolidation of metal per C.yd., including collection of gravel to be quoted separately.				

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 1st March 1938.

The attention of the public is invited to the Notification published in pages 350-352, Part VI of the *Mysore Gazette* dated 10th March 1938 calling for tenders for the work of "Forming a new road connecting Koppa-Balgady Road with Tarikere-Mangalore Road and constructing a Girder bridge across Musarehalla on Koppa-Balgady Road."

The last date of receipt of tender in this office is 21st March 1938.

Abstract Notification dated 4th March 1938.

The attention of the public is invited to the Notification published in pages 353-355, Part VI of the *Mysore Gazette* dated 10th March 1938, calling for tenders for the work of constructing a Maternity Hospital at Kadur.

The last date of receipt of tender in this office is 26th March 1938.

Notification dated 12th March 1938.

1. Sealed tenders will be received at the office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 2nd April 1938, for constructing a Girder Bridge across Makkikoppa Halla on Sollebyle-Balehole Road.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Kadur Division, Chikmagalur, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, and should be superscribed as "Tenders for constructing a Girder Bridge across Makkikoppa Halla on Sollebyle-Balehole Road." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a deposit of Rs. 560 (rupees five hundred and sixty only) in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days, between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amount for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised, and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department for the current schedule of rates.

13. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimates are only approximate and are liable to alteration, omissions, deductions, or additions at the discretion of the Executive Engineer, Kadur Division, or his representative. The tendered rates will hold good for any quantity whether it is higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and be handed over to the Public Works Department by the end of June 1939, failing which the Executive Engineer may, at his discretion, levy a penalty up to Rs. 100 which will be recovered from the contractor's outstandings for the period exceeded by him over the time specified above.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quantity of work, etc., the decision of the Executive Engineer, Kadur Division, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application to the Executive Engineer, Kadur Division, Chikmagalur.

19. No claims for damages for delays caused by officers of the department in the execution of work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the Departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools, plant and machinery that will be supplied by the department in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer, and the tenderer will pay the hire, etc., on machinery at the perscribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant

from the Stores to the date of return to the Stores, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Abstract estimate for constructing a Girder Bridge across Makkikoppa Halla on Sollebyle-Balehole Road.

No.	Description of work	Unit	Quantity
1	Clearing site of Bridge and forming	L. S.	..
2	Earthwork excavation of foundations in hard soil	C.yds.	448
3	Benching in hard rock to seat of foundations	L. S.	..
4	Burnt stone jelly in surki cement mortar concrete for foundations (1 : 6)	C.ft.	1,505
5	Burnt size stone in composite mortar surki and cement in 1 : 8 proportion complete with bond stones	,,	7,273
5(*a*)	Do do in surki mortar, etc., with bond stones	,,	7,273
6	Burnt size stone in composite mortar 1 : 8 for cut waters completely dressed as per design	,,	218
6(*a*)	Do do in surki mortar	,,	218
7	Providing and casting 1 : 3 : 6 cement concrete bearing slabs with exposed faces finished smooth	,,	84
8	Providing and fixing R. S. Girders of Tata's tested quality complete with one coat of anti-corrosive paint, 33 (22″×7″×75 lbs.) (3×2=6 girders)	Cwts.	132.5
9	R.C.C. deck slabs (1 : 2 : 4) proportion complete cost in site on the R. S. beams finished with camber, etc., as per design including centering charges, etc., complete	C.ft.	712
10	R.C. ornamental pilasters, complete finished as per design	No.	10
11	Hand railing with 1½″ G. I. pipes in T. iron upright, complete fixed into decking as per sanctioned design	R.ft.	128
12	Providing ½″ expansion joints to R.C.C. decking	,,	51
13	Cement pointing to masonry with 1 : 3 cement mortar after racking joints	Sqr.	22.60
14	Bailing out water during construction	L. S.	..
15	Burnt stone slabs 6″ thick nicely dressed laid in cement surki mortar 1 : 8 over returns	Sq.ft.	184
15(*a*)	Do do with surki mortar	Sq.ft.	184
16	Earthwork forming embankment for approach roads complete including lead of 100 yards	C.yds.	7,320
17	Collecting breaking and spreading quartz metal with lead, for approach road surface	,,	150
18	Do gravel	,,	50
19	Collecting and spreading sand	,,	25

C. R. IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 13th March 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M., on 25th March 1938, for the Extension of Civil Hospital at Chitaldrug towards the east. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 525 (Five hundred and twenty-five) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the Extension of Civil Hospital at Chitaldrug towards the east." The balance to make up 10 per cent being payable at the time of execution of the agreement, in default of which tenders will be rejected.